BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 01

Name of Work:-:Providing RCC covering slab to Main and Cross roads of G Ramaiah Enclave in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Vijayakumar R	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17)	Cum	60.60	80.66	Rupees eighty and paise sixty six only
2	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32)	sqm	243.00	60.66	Rupees sixty and paise sixty six only
3	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33)	Sqm	243.00	74.66	Rupees seventy four and paise sixty six only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick(P.No 25 I.No 5.31.1)	sqm	81.00	619.66	Rupees six hundred nineteen and paise sixty six only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications (Item no17.1,Page no133,PWD SR 2016-17	Cum	60.60	66.66	Rupees sixty six and paise sixty six only
6	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	48.00	927.66	Rupees nine hundred twenty seven and paise sixty six only

Executive Engineer Yelhanka Zone

CE : xxxx

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Vijayakumar R	
				Rate	Rate in Words
	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Sqm	48.00	710.66	Rupees seven hundred ten and paise sixty six only
8	KSRRB 4.1:6Providing and laying in position plain **cement concrete mix 1:2:4** with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no4.1,4.2 **(Page.12 & Item No. 4.6)**	Cum	13.20	5386.66	Rupees five thousand three hundred eighty six and paise sixty six only
9	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	226.80	1399.66	Rupees one thousand three hundred ninety nine and paise sixty six only

V; Iyakumar R
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Yelahanka Zone